

GENERAL LANDSCAPING NOTES FOR ALL SHEETS

- ALL CONTRACTORS WISHING TO SUBMIT BIDS FOR THIS LANDSCAPING PROJECT SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL CONDITIONS.
- PROTECT THE IMPROVEMENTS ON SITE AND ON THE ADJOINING PROPERTIES. PROVIDE BARRICADES, COVERINGS OR OTHER TYPE OF PROTECTION AS NECESSARY TO PREVENT DAMAGE AND TO SAFEGUARD AGAINST INJURY TO EXISTING UTILITIES.
- DAMAGE THAT OCCURS TO PLANTS DURING TRANSPORTATION AND INSTALLATION WILL BE THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR.
- ALL PLANTING BEDS SHALL BE INSTALLED WITH 3" OF 2" CRUSHED ROCK MULCH, LANDSCAPE FABRIC WITH A MINIMUM WEIGHT OF 4 OZ./SY, AND WHEREVER NECESSARY, 6" COMMERCIAL GRADE BLACK PLASTIC EDGING TO CONTAIN THE PLANTING BED.
- ALL LANDSCAPE PLANTINGS ARE TO BE WATERED BY THE LANDSCAPE CONTRACTOR THE SAME DAY THAT THE PLANTING OCCURS. THE OWNER WILL BE RESPONSIBLE FOR PROVIDING WATER FOR THIS TASK. IF WATER IS NOT AVAILABLE AT THE BUILDING, THE LANDSCAPE CONTRACTOR SHALL PROVIDE ALTERNATIVE METHODS FOR WATERING.
- SOLITARY TREES DO NOT NEED TO BE EDGED AROUND, HOWEVER ORGANIC WOOD MULCH SHALL BE PLACED AROUND THE TREE IN A MUTTLE RING THAT CONFORMS TO THE DETAIL PROVIDED FOR TREE
- CONTRACTOR SHALL PROVIDE WRITTEN WARRANTIES CONFIRMING THE FOLLOWING:
- (L9) LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR WATERING AND CARING FOR ALL PLANT
- ALL PORTIONS OF THE SITE NOT RECEIVING OTHER IMPROVEMENTS SHALL BE SEEDED AND HYDROMULCHED ACCORDING TO CITY OF BISMARCK SPECIFICATIONS FOR CLASS II SEED. CONTRACTOR SHALL PAY PARTICULAR ATTENTION TO SEED ESTABLISHMENT, SEED STAND ACCEPTANCE, AND RESEEDING AND REPAIR PORTIONS OF THE SPECIFICATION. DELETE THE SECTION DISCUSSING

- BACKFILL AROUND

PRUNE DAMAGED OR DEAD WOOD IMMEDIATELY PRIOR TO PLANTING. PAINT

ALL CUTS OVER I" DIA.

DOUBLE STRAND #12 GA.

WRE WRE ADJUST TENSION
BY TWISTING WIRE. ALLOW
SOME MOVEMENT OF TRUNK.
2-PLY RUBBER HOSE OR
EQUIVALENT TREE STRAP.

- SET CROWN OF ROOTBALL AT FINISH

GRADE. UNTIE BURLAP FROM BASE OF TRUNK

ROUGHEN THE EDGES OF HOLE BEFORE

- SET ROOTBALL ON

SUBGRADE TO PREVENT

MULCH 3" DEEP WITH

CITY FORESTER 10-24-17

1-800-795-0555

TRIM AS NECESSARY

- (TI) ANY TOPSOIL STOCKPILED ON SITE SHALL BE AVAILABLE FOR THE LANDSCAPE CONTRACTOR TO SPREAD AND FINISH GRADE. ALL PORTIONS OF THE SITE NOT RECEIVING CONCRETE, CURB & GUTTER OR OTHER IMPROVEMENTS SHALL BE COVERED WITH A MINIMUM OF 6" OF TOPSOIL AND SEEDED ACCORDING TO
- T2 ALL IMPORTED TOPSOIL SHALL BE NATURAL, FRIABLE, FERTILE, FINE, SANDY-LOAM TOPSOIL. IT SHALL BE FREE FROM SUBSOIL, NOXIOUS WEEDS, STONES, LIME, CEMENT, ASHES, SLAG, OR OTHER
- EROSION. BACKFILL BEHIND CURB AND GUTTERS AND SIDEWALK AS SOON AS REASONABLE TO PREVENT STANDING WATER AND PROTECT THE IMPROVEMENTS.

PAVEMENT

- (P1) ON SITE EXTERIOR CONCRETE MATERIALS AND CONSTRUCTION MATERIALS SHALL CONFORM TO CITY OF BISMARCK SPECIFICATIONS EXCEPT AS MODIFIED HEREIN. AIR CONTENT SHALL BE 5% TO 7%.
- P2 CITY SIDEWALK PER CITY OF BISMARCK SPECIFICATIONS THICKEN SIDEWALK AT DRIVEWAYS TO 8" AND
- SST STRIPING SHALL BE 4" WIDE NON REFLECTORIZED PAINT MEETING THE REQUIREMENTS OF AASHTO M28 APPLIED AT A RATE OF 110 SQUARE FEET PER GALLON. COLOR SHALL BE YELLOW. TYPICAL FOR ALL STRIPING UNLES OTHERWISE NOTED.
- SS2 ADA STRIPING FOR LANES AND SYMBOLS SHALL BE BLUE PAINT MEETING THE REQUIREMENT OF AASHTO M28 APPLIED AT A RATE OF 110 SQUARE FEET PER GALLON. PAINT FACE AND TOP OF CURB (6" WIDE) IN FRONT OF ALL HANDICAP STALLS.
- SS3 PROVIDE AND INSTALL ADA SIGNS AND POSTS.


FENCE NOTES

 \langle F1 \rangle INSTALL 6' OPAQUE WOOD FENCE WITH GATE TO THE EAST.

PLANT PALETTE

| | SYM. | COMMON NAME | SCIENTIFIC NAME | SIZE | QNTY. |
|--------|----------|-----------------------------------------|-----------------------------------------------------|-----------------|--------|
| TREES | BH SG | BLACK HILLS SPRUCE SIENNA GLEN MAPLE | Picea glauca var. densata Acer fremanii 'Sienna' | 4' + 2" Cal. | 6 7 |
| SHRUBS | AC | ALPINE CURRANT | Ribes alpinum | 2 Gallon | 56 |

st—st—st— EXISTING STORM SEWER EXISTING ASPHALT EXISTING CONCRETE - EXISTING CONTOUR



OCTOBER 11, 2013

SCALE - 1"=20' NAVD 88 DATUM

SWENSON HAGEN & CO

THIS DOCUMENT WAS ORIGINALLY SEALED BY LASON R. PETRYSZYN, PE, ON LOUIS AND THE ORIGINAL DOCUMENT IS STORED AT THE OFFICE OF SWENSON, HAGEN & CO.

DRAWN BY: CK CHECK BY: JP DATE: 10/11/2013 FILE DESC: _____ EASTDALE ADDITION COMPUTER FILE: L13DB4.DWG SURVEY FILE:

HAGEN

ZEE

8 2 E

SHEET

FURNISHED TREES AND SHRUBS GUARANTEED TO LIVE AND REMAIN STRONG, VIGOROUS, AND HEALTHY CONDITION FOR 365 DAYS MINIMUM FROM DATE LANDSCAPE INSTALLATION IS ACCEPTED AS COMPLETED.

MATERIAL, SEED, SOD, AND OTHER LANDSCAPING IMPROVEMENTS UNTIL THE DATE OF FINAL INSPECTION

MAINTENANCE OF ACCEPTED SEED STAND.

TOPSOIL NOTES

- TOPSOIL SHALL BE PLACED AND SEEDED AS SOON AS PRACTICAL TO MINIMIZE WIND AND WATER

- STRENGTH AT 28 DAYS SHALL BE 4000 PSI.
- PROVIDE KEYWAY PER CITY SPECIFICATIONS.
- (P3) 5" CONCRETE WITH FIBERMESH. SEE DETAIL.

SIGNAGE AND STRIPING

PROPOSED CONCRETE